


Rev. no.	Rev. description	Date	Sign	Chk'd
•		•	•	

Legend



Existing trees to be retained, mulched at base with fine bark and soil enricher mix to 50mm depth, min 2m \varnothing



Proposed wildflower meadow to develop naturally, Additional plug planting into existing meadow (425m²), see plant list



Proposed muscari bulb planting into existing meadow



Existing underground services (approximate locations).
Contractor responsible for locating and screening for services before starting work on site

This drawing to be read in conjunction with other drawings and specifications issued with this tender
All Rumex obtusifolius to be removed from site

Plant List

Wildflower meadow - to develop naturally(see maintenance) with additional annual planting to include plug size plants with compost volume 4-5cm deep x 3-4cm square planted throughout roundabout Cosmos bipinnatus sensation plug 1.5/m² 1.5/m² 640 Leucanthemum vulgare

Grape Hyacinth bulb planting - Muscari latifolium planted at 50/m², 4,500 no. (90m²) see legend for location





Comhairle Cathrach & Contae **Luimnigh Limerick** City & County Council

Limerick City and County Council Landscape Designs and Maintenance Plans for Limerick City Roundabouts

3- Killmalock Roundabout Tender Stage Hardworks and Softworks Stage

Drg. No.: T399-113 Scale: 1:100@A1 Date: 2020, June 24th

Drawn By: MW Checked by: DR



12 Barrington Street Tel.: 061 59 00 01 Limerick Mob.: 087 314 5 70 www.daveryan.ie Email: info@daveryan.ie